

COMPLETED WORK:

- A. DELIVER COMPLETED WORK AS CALLED FOR BY THE CONTRACT TO THE OWNER FREE FROM LIENS, CLAIMS OR ENCUMBRANCES OF ANY DESCRIPTION WHATSOEVER AGAINST THE OWNER. ACCEPTANCE OF SUCH WORK IS DEFINED AS APPROVAL OF FINAL PAYOUT.
- B. IF OWNER RECEIVES "NOTICE OF CLAIM" TO BE FILED OR IF A CLAIM IS FILED AS A RESULT OF CONTRACTOR'S NON-PAYMENT, OWNER POSSESSES THE RIGHT UNDER THE CONSTRUCTION CONTRACT TO EITHER SETTLE THE CLAIM AND DEDUCT SOME FROM THE CONTRACT SUM OR TO REQUIRE THE CONTRACTOR TO BOND OVER SUCH SMALL CLAIMS, INCLUDING ANY ASSOCIATED EXPENSES AS DEFINED IN THE CONSTRUCTION CONTRACT AND TO PROMPTLY DEFEND TO CONCLUSION OWNER AND OWNER'S INTEREST AGAINST SAID CLAIM OF CLAIMS.
- C. COMPLETION OF WORK ON THE PROJECT REQUIRES THE SUBMISSION BY THE CONTRACTOR OF CERTAIN DOCUMENTATION IN ORDER FOR THE FINAL RETENTION DRAW TO BE PAID TO THE CONTRACTOR. THE SUBMISSION OF THESE DOCUMENTS IS DEFINED IN THE CONSTRUCTION CONTRACT AND IS INCLUSIVE OF THE FOLLOWING ITEMS: RECORD DRAWINGS AND SPECIFICATIONS INCLUDING MICROFICHE COPIES; LIEN WAIVERS FROM CONTRACTOR AND SUB-CONTRACTORS AND MATERIAL MEN; LIST OF ALL SUBCONTRACTORS AND MATERIAL MEN; CONTRACTOR'S GUARANTEE AND COMPLETION AFFIDAVIT; FINAL SIGNED PUNCH LIST; ANY WORK ORDERS AND ASSOCIATED CONTRACT CHANGE ORDERS; CERTIFICATE OF OCCUPANCY AND ANY RELATED PUBLIC AGENCY; CERTIFICATION OF PROJECT COMPLETION; COPIES OF PROJECT INSPECTION REPORTS; PERMITTED SET OF DRAWINGS AND SPECIFICATION; ALL WARRANTIES; ALL CERTIFICATIONS NOTED IN THE DRAWINGS INCLUDING CIVIL DRAWINGS, THE BID DOCUMENTS AND CONSTRUCTION CONTRACT; AND ANY REQUIRED TEST AND/OR ENGINEERING REPORTS.

- MAINTENANCE AND CLEANING:
- A. THROUGHOUT THE PERIOD OF CONSTRUCTION, BE RESPONSIBLE FOR SATISFACTORILY MAINTAINING THE PREMISES IN A NEAT AND CLEAN CONDITION. THIS MEANS THE TIMELY REMOVAL OF ALL REFUSE AND DEBRIS FROM THE PREMISES.
- B. STORE ALL EQUIPMENT AND MATERIALS IN A NEAT MANNER AND PROTECT THEM FROM ANY DAMAGE FROM THE ELEMENTS. MAINTAIN BUILDING IN A GENERALLY CLEAN CONDITION DURING THE PERIOD OF CONSTRUCTION, AND UPON FINAL COMPLETION PROVIDE A PROFESSIONAL SERVICE TO THOROUGHLY CLEAN ALL GLASS, FLOORS, FURNITURE AND EQUIPMENT.

CHANGES:

- A. THE OWNER, WITHOUT INVALIDATING THE CONTRACT, MAY ORDER CHANGES IN THE WORK WITHIN THE GENERAL SCOPE OF THE CONTRACT, CONSISTING OF ADDITIONS, DELETIONS, OR OTHER REVISION. THE CONTRACT SUM AND THE CONTRACT TIME WILL BE ADJUSTED ACCORDINGLY. AN OWNER CONTRACT CHANGE ORDER MAY BE ISSUED BY AN OWNER'S CONSTRUCTION MANAGER BUT MUST BE APPROVED BY THE VICE PRESIDENT FACILITY DEVELOPMENT PRIOR TO PAYMENT, FOR CORPORATE PROJECTS.
- B. THE COST OR CREDIT TO THE OWNER RESULTING FROM A CHANGE IN THE WORK WILL BE DETERMINED BY MUTUAL AGREEMENT. PERFORM ALL WORK UNDER THE APPLICABLE CONDITINS OF THE CONTRACT DOCUMENTS.
- C. OBTAIN WRITTEN AUTHORIZATION FOR CHANGES IN THE WORK (CONSTRUCTION WORK ORDER) FROM THE OWNER'S CONSTRUCTION MANAGER PRIOR TO COMPLETION OF THE WORK.

GUARANTEE:

- A. A FULLY AND UNCONDITIONALLY GUARANTEE ALL LABOR, MATERIALS, AND EQUIPMENT REQUIRED BY THE OWNER - CONTRACTOR AGREEMENT(S) FOR A PERIOD OF ONE (1) YER FROM THE DATE OF FINAL ACCEPTANCE OR THE DATE THE RESTAURANT IS OPENED FOR BUSINESS BY THE OWNER.

SECTION 030000 - CAST-IN-PLACE CONCRETE

REFER TO STRUCTURAL DRAWINGS FOR SPECIFICATION

SECTION 048100 - UNIT MASONRY

PART 1 - GENERAL

1.1 SUMMARY

- A. THIS SECTION INCLUDES UNIT MASONRY ASSEMBLIES CONSISTING OF THE FOLLOWING:
1. MODIFICATION OF EXISTING CONCRETE MASONRY UNITS IF REQUIRED.
 2. SEE DIVISION 5 SECTION "METAL FABRICATIONS" FOR FURNISHING STEEL LINTELS INSTALLED IN UNIT MASONRY ASSEMBLIES
- B. SEE DIVISION 07 SECTION "SHEET METAL FLASHING AND TRIM" FOR FURNISHING MANUFACTURED REGLETS INSTALLED IN MASONRY JOINTS FOR METAL FLASHING.

1.2 PROJECT CONDITIONS

- A. COLD-WEATHER REQUIREMENTS: DO NOT USE FROZEN SUBSTRATES. REMOVE AND REPLACE UNIT MASONRY DAMAGED BY FROST OR BY FREEZING CONDITIONS. COMPLY WITH COLD-WEATHER CONSTRUCTION REQUIREMENTS CONTAINED IN ACI 530.1/ASCE 6/TMS 602.
- B. HOT-WEATHER REQUIREMENTS: WHEN AMBIENT TEMPERATURE EXCEEDS 100 DEG F, OR 90 DEG F WITH A WIND VELOCITY GREATER THAN 8 MPH, DO NOT SPREAD MORTAR BEDS MORE THAN 48 INCHES AHEAD OF MASONRY. SET MASONRY UNITS WITHIN ONE MINUTE OF SPREADING MORTAR. COMPLY WITH HOT-WEATHER CONSTRUCTION REQUIREMENTS CONTAINED IN ACI 530.1/ASCE 6/TMS 602.

PART 2 - PRODUCTS

2.1 MANUFACTURER, COLOR, AND TEXTURE

- A. AS SPECIFIED ON DRAWINGS.

2.2 MASONRY UNITS

- A. CONCRETE MASONRY UNITS: ASTM C 90.
1. UNIT COMPRESSIVE STRENGTH: 2800 PSI MINIMUM, AVERAGE NET-AREA COMPRESSIVE STRENGTH.
 2. WEIGHT CLASSIFICATION: NORMAL WEIGHT BELOW GRADE AND ABOVE GRADE FOR EXTERIOR EXPOSURE.
 3. SPECIAL SHAPES: PROVIDE FOR LINTELS, CORNERS, JAMBS, SASH, CONTROL JOINTS, HEADERS, BONDING, AND OTHER SPECIAL CONDITIONS.
 4. INTEGRAL WATER REPELLENT: PROVIDE UNITS MADE WITH LIQUID POLYMERIC, INTEGRAL WATER REPELLENT ADMIXTURE THAT DOES NOT FLEXURAL BOND STRENGTH FOR EXPOSED UNITS.
 - a. PRODUCTS: SUBJECT TO COMPLIANCE WITH REQUIREMENTS
 1. ACM CHEMISTRIES; RAINBLOC
 2. BASF; RHEOPEL PLUS
 3. W.R. GRACE & CO.; DRY-BLOCK
- B. BRICK, GENERAL:
1. PROVIDE UNITS WITHOUT CORES OR FROGS AND WITH EXPOSED SURFACES FINISHED FOR ENDS OF SILLS AND CAPS AND FOR SIMILAR APPLICATIONS THAT WOULD OTHERWISE EXPOSE UNFINISHED BRICK SURFACES.
 2. PROVIDE SPECIAL SHAPES FOR APPLICATIONS REQUIRING BRICK OF SIZE, FORM, COLOR, AND TEXTURE ON EXPOSED SURFACES THAT CANNOT BE PRODUCED BY SAWING.
- C. FACE BRICK: ASTM C 216, GRADE SW, TYPE FBS.

1. UNIT COMPRESSIVE STRENGTH: 4400 PSI MINIMUM AVERAGE, NET-AREA COMPRESSIVE STRENGTH.
2. INITIAL RATE OF ABSORPTION: LESS THAN 20 G/30 SQ. IN. PER MINUTE WHEN TESTED PER ASTM C 67.
- EFFLORESCENCE: WHEN TESTED PER ASTM C 67 AND BRICK IS RATED "NOT EFFLORESCED."
4. SURFACE COLORING: BRICK WITH SURFACE COLORING, OTHER THAN FLASHED OR SAND-FINISHED BRICK, WILL WITHSTAND 50 CYCLES OF FREEZING AND THAWING PER ASTM C 67 WITH NO OBSERVABLE DIFFERENCE IN THE APPLIED FINISH WHEN VIEWED FROM 10 FEET.
5. SIZE: AS INDICATED ON DRAWINGS.

2.3 MORTAR AND GROUT MATERIALS

- A. PORTLAND CEMENT: ASTM C 150, TYPE I OR II, EXCEPT TYPE III MAY BE USED FOR COLD-WEATHER CONSTRUCTION.
- B. HYDRATED LIME: ASTM C 207, TYPE S.
- C. AGGREGATE FOR MORTAR: ASTM C 144; EXCEPT FOR JOINTS LESS THAN 1/4 INCH THICK, USE AGGREGATE GRADED WITH 100 PERCENT PASSING THE NO. 16 SIEVE.
- D. AGGREGATE FOR GROUT: ASTM C 404.
- E. MORTAR PIGMENTS: AS SPECIFIED ON DRAWINGS.
- F. WATER: POTABLE.

2.4 REINFORCING STEEL

- A. UNCOATED STEEL REINFORCING BARS: ASTM A 615; ASTM A 615M.
- B. MASONRY JOINT REINFORCEMENT: ASTM A 951; MILL GALVANIZED, CARBON-STEEL WIRE FOR INTERIOR WALLS AND HOT-DIP GALVANIZED, CARBON-STEEL WIRE FOR EXTERIOR WALLS.
4. WIRE SIZE FOR SIDE RODS: W1.7 OR 0.148-INCH DIAMETER.
 5. WIRE SIZE FOR CROSS RODS: W1.7 OR 0.148-INCH DIAMETER.
 6. SINGLE-WYTHE MASONRY: USE EITHER LADDER OR TRUSS TYPE WITH SINGLE PAIR OF SIDE RODS AND CROSS RODS SPACED NOT MORE THAN 16 INCHES O.C.

2.5 TIES AND ANCHORS

- A. MATERIALS, GENERAL: AS FOLLOWS, UNLESS OTHERWISE INDICATED.
1. GALVANIZED, CARBON-STEEL WIRE: ASTM A 82; WITH ASTM A 153, CLASS B-2 COATING FOR EXTERIOR WALLS AND CLASS 1 COATING FOR INTERIOR WALLS.
 2. GALVANIZED STEEL SHEET: ASTM A 366 COLD-ROLLED, CARBON-STEEL SHEET HOT-DIP GALVANIZED AFTER FABRICATION TO COMPLY WITH ASTM A 153 AT EXTERIOR WALLS; AND ASTM A 653, 660, COMMERCIAL-QUALITY, STEEL SHEET ZINC COATED BY HOT-DIP PROCESS ON CONTINUOUS LINES BEFORE FABRICATION AT INTERIOR WALLS.
- B. ADJUSTABLE MASONRY-VENEER ANCHORS
1. PROVIDE 2-PIECE ASSEMBLIES THAT ALLOW VERTICAL OR HORIZONTAL ADJUSTMENT BUT RESIST TENSION AND COMPRESSION FORCES PERPENDICULAR TO WALL, FOR ATTACHMENT OVER SHEATHING TO WOOD OR METAL STUDS, AND THAT ARE CAPABLE OF WITHSTANDING A 100-LBF LOAD IN BOTH TENSION AND COMPRESSION WITHOUT DEFORMING OR DEVELOPING PLAY IN EXCESS OF 0.05 INCH.

2.6 EMBEDDED FLASHING MATERIALS

- A. CONCEALED FLASHING: FOR FLASHING PARTLY EXPOSED TO THE EXTERIOR, USE METAL FLASHING SPECIFIED ABOVE. FOR FLASHING NOT EXPOSED TO THE EXTERIOR, USE THE FOLLOWING, UNLESS OTHERWISE INDICATED:

1. COPPER-LAMINATED FLASHING: MANUFACTURER'S STANDARD LAMINATED FLASHING CONSISTING OF 7-0Z/SQ. FT. SHEET COPPER BONDED WITH ASPHALT BETWEEN 2 LAYERS OF GLASS-FIBER CLOTH.

2.7 MISCELLANEOUS MASONRY ACCESSORIES

- A. COMPRESSIBLE FILLER: PREMOLDED FILLER STRIPS COMPLYING WITH ASTM D 1056, GRADE 2A1; COMPRESSIBLE UP TO 35 PERCENT; FORMULATED FROM NEOPRENE.
- B. RECTANGULAR PLASTIC WEEP/VENT TUBING: CLEAR BUTYRATE, 3/8 BY 1-1/2 BY 3-1/2 INCHES.

2.8 MASONRY CLEANERS

- A. PROPRIETARY ACIDIC CLEANER: MANUFACTURER'S STANDARD-STRENGTH CLEANER DESIGNED FOR REMOVING MORTAR/GROUT STAINS, EFFLORESCENCE, AND OTHER NEW CONSTRUCTION STAINS FROM NEW MASONRY WITHOUT DISCOLORING OR DAMAGING SURFACES. USE PRODUCT APPROVED FOR INTENDED USE BY CLEANER MANUFACTURER AND MANUFACTURER OF MASONRY UNITS BEING CLEANED.

2.9 CAVITY DRAINAGE MATERIAL

- A. FREE-DRAINING MESH, MADE FROM POLYMER STRANDS THAT WILL NOT DEGRADE WITHIN THE WALL CAVITY.
1. PROVIDE ONE OF THE FOLLOWING CONFIGURATIONS:
 - a. STRIPS, FULL-DEPTH OF CAVITY AND 10 INCHES (250 MM) WIDE, WITH DOVETAIL SHAPED NOTCHES 7 INCHES (175 MM) DEEP.
 - b. STRIPS, NOT LESS THAN 1-1/2 INCHES (38 MM) THICK AND 10 INCHES (250 MM) WIDE, WITH DIMPLED SURFACE DESIGNED TO CATCH MORTAR DROPPINGS AND PREVENT WEEP HOLES FROM BEING CLOGGED WITH MORTAR.
 - c. SHEETS OR STRIPS FULL DEPTH OF CAVITY AND INSTALLED TO FULL HEIGHT OF CAVITY.
 2. AVAILABLE PRODUCTS:
 - a. ADVANCED BUILDING PRODUCTS INC.; MORTAR BREAK OR MORTAR BREAK II.
 - b. ARCHOVATIONS, INC.; CAVCLEAR MASONRY MAT.
 - c. DAYTON SUPERIOR CORPORATION, DUR-O-WAL DIVISION; POLYTITE MORTARSTOP.
 - d. MORTAR NET USA, LTD.; MORTAR NET.

2.10 MORTAR AND GROUT MIXES

- A. GENERAL: DO NOT USE ADMIXTURES, UNLESS OTHERWISE INDICATED. DO NOT USE CALCIUM CHLORIDE IN MORTAR OR GROUT.
- B. MORTAR FOR UNIT MASONRY: COMPLY WITH ASTM C 270, PROPORTION SPECIFICATION.
- C. GROUT FOR UNIT MASONRY: COMPLY WITH ASTM C 476.
1. PROVIDE GROUT WITH A SLUMP OF 8 TO 11 INCHES AS MEASURED ACCORDING TO ASTM C 143.
- D. WATER REPELLENT ADMIXTURE: LIQUID WATER-REPELLENT MORTAR ADMIXTURE INTENDED FOR USE WITH CMU'S CONTAINING INTEGRAL WATER REPELLENT BY SAME MANUFACTURER.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. CUT MASONRY UNITS WITH MOTOR-DRIVEN SAWS. ALLOW UNITS CUT WITH WATER-COOLED SAWS TO DRY BEFORE PLACING, UNLESS WETTING OF UNITS IS SPECIFIED. INSTALL CUT UNITS WITH CUT SURFACES AND, WHERE POSSIBLE, CUT EDGES CONCEALED.
- B. SELECT AND ARRANGE UNITS FOR EXPOSED UNIT MASONRY TO PRODUCE A UNIFORM BLEND OF COLORS AND TEXTURES.
- C. WETTING OF UNITS: WET BRICK BEFORE LAYING IF THE INITIAL RATE OF ABSORPTION EXCEEDS 30 G/30 SQ. IN. PER MINUTE WHEN TESTED PER ASTM C 67. ALLOW UNITS TO ABSORB WATER SO THEY ARE DAMP BUT NOT WET AT TIME OF LAYING. DO NOT WET CONCRETE MASONRY UNITS.
- D. COMPLY WITH TOLERANCES IN ACI 530.1/ASCE 6/TMS 602 AND THE FOLLOWING:
1. FOR CONSPICUOUS VERTICAL LINES, SUCH AS EXTERNAL CORNERS, DOOR JAMBS, REVEALS, AND EXPANSION AND CONTROL JOINTS, DO NOT VARY FROM PLUMB BY MORE THAN 1/4 INCH IN 20 FEET OR 1/2 INCH MAXIMUM.
 2. FOR CONSPICUOUS HORIZONTAL LINES, SUCH AS LINTELS, SILLS, PARAPETS, AND REVEALS, DO NOT VARY FROM LEVEL BY MORE THAN 1/4 INCH IN 20 FEET, OR 1/2 INCH MAXIMUM.

3.2 LAYING MASONRY WALLS

- A. LAY OUT WALLS IN ADVANCE FOR ACCURATE SPACING OF SURFACE BOND PATTERNS WITH UNIFORM JOINT THICKNESSES AND FOR ACCURATE LOCATION OF OPENINGS, MOVEMENT-TYPE JOINTS, RETURNS, AND OFFSETS. AVOID USING LESS-THAN-HALF-SIZE UNITS, PARTICULARLY AT CORNERS, JAMBS, AND, WHERE POSSIBLE, AT OTHER LOCATIONS.
1. CONCRETE MASONRY UNITS: ONE-HALF RUNNING BOND.
 2. FACE BRICK: AS INDICATED ON DRAWINGS.

3.3 JOINTING

- A. TOOL EXPOSED JOINTS SLIGHTLY CONCAVE WHEN THUMBPRINT HARD, USING A JOINTER LARGER THAN JOINT THICKNESS, UNLESS OTHERWISE INDICATED.

3.4 CAVITIES

- A. KEEP CAVITIES CLEAN OF MORTAR DROPPINGS AND OTHER MATERIALS DURING CONSTRUCTION.

3.5 ANCHORING MASONRY

- A. ANCHOR MASONRY VENEERS TO WALL FRAMING WITH MASONRY-VENEER ANCHORS TO COMPLY WITH THE FOLLOWING REQUIREMENTS:
1. FASTEN EACH ANCHOR SECTION THROUGH TO WALL FRAMING WITH TWO METAL FASTENERS OF TYPE INDICATED.
 2. SPACE ANCHORS AS INDICATED, BUT NOT MORE THAN 16 INCHES O.C. VERTICALLY AND 16 INCHES O.C. HORIZONTALLY WITH NOT LESS THAN 1 ANCHOR FOR EACH 1.77 SQ. FT. OF WALL AREA. INSTALL ADDITIONAL ANCHORS WITHIN 12 INCHES OF OPENINGS AND AT INTERVALS, NOT EXCEEDING 36 INCHES, AROUND PERIMETER.

3.6 FLASHING, WEEP HOLES AND VENTS

- A. GENERAL: INSTALL EMBEDDED FLASHING AND WEEP HOLES IN MASONRY AT SHELF ANGLES, LINTELS, LEDGES, OTHER OBSTRUCTIONS TO DOWNWARD FLOW OF WATER IN WALL, AND WHERE INDICATED.
1. EXTEND FLASHING 4 INCHES AT ENDS AND TURN FLASHING UP NOT LESS THAN 2 INCHES TO FORM A PAN.
- B. INSTALL WEEP HOLES IN THE HEAD JOINTS IN EXTERIOR WYTHES OF THE FIRST COURSE OF MASONRY IMMEDIATELY ABOVE EMBEDDED FLASHING. INSTALL VENTS IN VERTICAL HEAD JOINTS AT THE TOP OF EACH CONTINUOUS CAVITY AT SPACING INDICATED.
1. USE RECTANGULAR PLASTIC TUBING TO FORM WEEP HOLES.
 2. SPACE WEEP HOLES 24 INCHES O.C.
 3. TRIM WICKING MATERIAL USED IN WEEP HOLES FLUSH WITH OUTSIDE FACE OF WALL AFTER MORTAR HAS SET.

- 3.7 CLEANING
- A. CLEAN UNIT MASONRY BY DRY BRUSHING TO REMOVE MORTAR FINS AND SMEARS BEFORE TOOLING JOINTS, AS WORK PROGRESSES.
- B. AFTER MORTAR IS THOROUGHLY SET AND CURED, CLEAN EXPOSED MASONRY AS FOLLOWS:
1. PROTECT ADJACENT SURFACES FROM CONTACT WITH CLEANER.
 2. WET WALL SURFACES WITH WATER BEFORE APPLYING CLEANERS; REMOVE CLEANERS PROMPTLY BY RINSING SURFACES THOROUGHLY WITH CLEAR WATER.
 3. CLEAN MASONRY WITH A PROPRIETARY ACIDIC CLEANER APPLIED ACCORDING TO MANUFACTURER'S WRITTEN INSTRUCTIONS.

- 3.8 MASONRY WASTE DISPOSAL
- A. WASTE DISPOSAL: DISPOSE OF CLEAN MASONRY WASTE, INCLUDING BROKEN MASONRY UNITS, WASTE MORTAR AND EXCESS OR SOIL-CONTAMINATED SAND, AND OTHER MASONRY WASTE, AND LEGALLY DISPOSE OF OFF OWNER'S PROPERTY.

SECTION 051200 - STRUCTURAL STEEL FRAMING

REFER TO STRUCTURAL DRAWINGS FOR SPECIFICATION

SECTION 054000 - COLD FORMED METAL FRAMING

REFER TO STRUCTURAL DRAWINGS FOR SPECIFICATION

SECTION 055000 - METAL FABRICATIONS

PART 1 - GENERAL

1.1 SUMMARY

- A. THIS SECTION INCLUDES THE FOLLOWING:
1. MISCELLANEOUS STEEL FRAMING AND SUPPORTS.
 2. LOOSE BEARING AND LEVELING PLATES.
 3. STEEL LADDERS.
 4. LOOSE STEEL LINTELS. (REFER TO STRUCTURAL DRAWINGS FOR LOOSE STEEL LINTEL SPECIFICATION)
 5. SHELF ANGLES.
 6. TRASH ENCLOSURE GATES.
 7. CATCH BASIN FRAME AND GRATE. (REFER TO CIVIL PLANS.)
 8. PIPE GUARDS.
 9. PIPE BOLLARDS.

PART 2 - PRODUCTS

2.1 METALS

- A. METAL SURFACES, GENERAL: PROVIDE MATERIALS WITH SMOOTH, FLAT SURFACES WITHOUT BLEMISHES.
- B. FERROUS METALS:
1. STEEL PLATES, SHAPES, AND BARS: ASTM A 36.
 2. STEEL PIPE: ASTM A 53, STANDARD WEIGHT (SCHEDULE 40), UNLESS ANOTHER WEIGHT IS INDICATED OR REQUIRED BY STRUCTURAL LOADS.

2.2 PAINT

- A. SHOP PRIMER FOR FERROUS METAL (INTERIOR APPLICATIONS): FAST-CURING, LEAD- AND CHROMATE-FREE, UNIVERSAL MODIFIED-ALKYD PRIMER COMPLYING WITH PERFORMANCE REQUIREMENTS IN FS-TT-P-664 AND COMPATIBLE WITH FINISH PAINT SYSTEMS INDICATED.

2.3 FABRICATION

- A. CONNECTIONS, GENERAL: USE CONNECTIONS THAT MAINTAIN STRUCTURAL VALUE OF JOINED PIECES.
1. SHEAR AND PUNCH METALS CLEANLY AND ACCURATELY. REMOVE BURRS.
 2. WELD CORNERS AND SEAMS CONTINUOUSLY. USE MATERIALS AND METHODS THAT MINIMIZE DISTORTION AND DEVELOP STRENGTH AND CORROSION RESISTANCE OF BASE METALS. OBTAIN FUSION WITHOUT UNDERCUT OR OVERLAP. REMOVE WELDING FLUX IMMEDIATELY. FINISH EXPOSED WELDS SMOOTH AND BLENDED.
 3. FABRICATE JOINTS THAT WILL BE EXPOSED TO WEATHER IN A MANNER TO EXCLUDE WATER, OR PROVIDE WEEP HOLES.
 4. FORM EXPOSED CONNECTIONS WITH HAIRLINE JOINTS, FLUSH AND SMOOTH, USING CONCEALED FASTENERS WHERE POSSIBLE. LOCATE JOINTS WHERE LEAST CONSPICUOUS.
- B. STEEL LADDERS: COMPLY WITH ANSI A14.3, UNLESS OTHERWISE INDICATED.
- C. CATCH BASIN FRAME AND GRATE: PROVIDE CATCH BASIN FRAME WITH TYPE "A" GRATE.
- D. PIPE BOLLARDS: FABRICATE FROM SCHEDULE 40 STEEL PIPE.
- E. TRASH ENCLOSURE GATES. AS SPECIFIED AND DETAILED ON DRAWINGS.

- 2.4 FINISHES
- A. FINISH METAL FABRICATIONS AFTER ASSEMBLY. COMPLY WITH NAAMM'S "METAL FINISHES MANUAL FOR ARCHITECTURAL AND METAL PRODUCTS" FOR RECOMMENDATIONS FOR APPLYING AND DESIGNATING FINISHES. SHOP PRIME FERROUS-METAL ITEMS NOT INDICATED TO BE GALVANIZED.

PART 3 - EXECUTION

3.1 INSTALLATION

1. GENERAL: PROVIDE ANCHORAGE DEVICES AND FASTENERS WHERE METAL FABRICATIONS ARE REQUIRED TO BE FASTENED TO IN-PLACE CONSTRUCTION.
 2. FIT EXPOSED CONNECTIONS ACCURATELY THROUGH. WELD CONNECTIONS, UNLESS OTHERWISE INDICATED. DO NOT WELD, CUT, OR ABRADE GALVANIZED SURFACES.
- B. BOLLARDS:
1. ANCHOR IN CONCRETE WITH PIPE SLEEVES PRESET AND ANCHORED INTO CONCRETE. FILL SPACE BETWEEN AND SLEEVE SOLIDLY WITH NONSHRINK, NONMETALLIC GROUT.
 2. FILL BOLLARDS SOLIDLY WITH CONCRETE, MOUNDING TOP SURFACE.
- C. TOUCH UP SURFACES AND FINISHES AFTER ERECTION.
1. PAINTED SURFACES: CLEAN FIELD WELDS, BOLTED CONNECTIONS, AND ABRADED AREAS AND TOUCH UP PAINT WITH THE SAME MATERIAL AS USED FOR SHOP PAINTING.

SECTION 061000 - ROUGH CARPENTRY

PART 1 - GENERAL

- 1.1 SUMMARY
- A. THIS SECTION INCLUDES THE FOLLOWING:
1. WOOD FRAMING (REFER TO STRUCTURAL DRAWINGS FOR WOOD FRAMING SPECIFICATIONS)
 2. WOOD SUPPORTS
 3. WOOD BLOCKING
 4. WOOD CANTS
 5. WOOD NAILERS
 6. WOOD FURRING
 7. WOOD GROUNDS
 8. WOOD SHEATHING (REFER TO STRUCTURAL DRAWINGS FOR WOOD SHEATHING SPECIFICATIONS)
 9. PLYWOOD BACKING PANELS

10.BUILDING WRAP

PART 2 - PRODUCTS

2.1 WOOD PRODUCTS, GENERAL

- A. LUMBER: DOC PS 20 AND APPLICABLE RULES OF GRADING AGENCIES CERTIFIED BY THE AMERICAN LUMBER STANDARDS COMMITTEE BOARD OF REVIEW.
1. FACTORY MARK EACH PIECE OF LUMBER WITH GRADE STAMP OF GRADING AGENCY.
 2. FOR EXPOSED LUMBER INDICATED TO RECEIVE A STAINED OR NATURAL FINISH, MARK GRADE STAMP ON END OR BACK OF EACH PIECE OR OMIT GRADE STAMP AND PROVIDE CERTIFICATES OF GRADE COMPLIANCE ISSUED BY GRADING AGENCY.
 3. PROVIDE DRY LUMBER WITH 15 PERCENT MAXIMUM MOISTURE CONTENT AT TIME OF DRESSING FOR 2-INCH NOMINAL THICKNESS OR LESS, UNLESS OTHERWISE INDICATED.
- B. ENGINEERED WOOD PRODUCTS: ACCEPTABLE TO AUTHORITIES HAVING JURISDICTION AND FOR WHICH CURRENT MODEL CODE RESEARCH OR EVALUATION REPORTS EXIST THAT SHOWS COMPLIANCE WITH BUILDING CODE IN EFFECT FOR PROJECT.
- C. WOOD STRUCTURAL PANELS:
1. PLYWOOD: DOC PS 1.
 2. ORIENTED STRAND BOARD: DOC PS 2.

2.2 WOOD-PRESERVATIVE-TREATED LUMBER

- A. PRESERVATIVE TREATMENT BY PRESSURE PROCESS: AWPA C2 (LUMBER) AND AWPA C9 (PLYWOOD), EXCEPT THAT LUMBER THAT IS NOT IN CONTACT WITH THE GROUND AND IS CONTINUOUSLY PROTECTED FROM LIQUID WATER MAY BE TREATED ACCORDING TO AWPA C21 WITH INORGANIC BORON (SBX).
- B. PRESSURE TREAT ALL LUMBER DESIGNATED AS 'TREATED' ON THE DRAWINGS AND/OR OTHER SECTIONS OF THESE SPECIFICATIONS TO CONFORM TO AWPA STANDARD C2. THE PRESENCE OF AWPB QUALITY MARK LP2 SHALL BE ACCEPTABLE AS EVIDENCE OF CONFORMANCE TO THIS SPECIFICATION.

2.3 DIMENSION LUMBER

- A. GENERAL: OF GRADES INDICATED ACCORDING TO THE AMERICAN LUMBER STANDARDS COMMITTEE NATIONAL GRADING RULE PROVISIONS OF THE GRADING AGENCY INDICATED.

- B. NON-LOAD-BEARING INTERIOR PARTITIONS: NO. 2 GRADE AND ANY OF THE FOLLOWING SPECIES:
1. MIXED SOUTHERN PINE; SPIB.
 2. NORTHERN SPECIES; NLGA.
 3. WESTERN WOODS; WCLIB OR WWPA.

2.4 MISCELLANEOUS LUMBER

- A. PROVIDE MISCELLANEOUS LUMBER FOR SUPPORT OR ATTACHMENT OF OTHER CONSTRUCTION, INCLUDING THE FOLLOWING:
1. ROOFTOP EQUIPMENT BASES AND SUPPORT CURBS.
 2. BLOCKING
 3. CANTS
 4. NAILERS
 5. FURRING
 6. GROUNDS
- B. FOR ITEMS OF DIMENSION LUMBER SIZE, PROVIDE NO. 2 GRADE LUMBER WITH 15 PERCENT MAXIMUM MOISTURE CONTENT.

2.5 ENGINEERED WOOD PRODUCTS

- A. LAMINATED-VENEER LUMBER: COMPOSITE OF WOOD VENEERS WITH GRAIN PRIMARILY PARALLEL TO MEMBER LENGTHS, MANUFACTURED WITH EXTERIOR-TYPE ADHESIVE COMPLYING WITH ASTM D 2559. ALLOWABLE DESIGN VALUES DETERMINED ACCORDING TO ASTM D 5456.

2.6 PLYWOOD BACKING PANELS

- A. TELEPHONE AND ELECTRICAL EQUIPMENT BACKING PANELS: DOC PS 1, EXPOSURE 1, C-D PLUGGED, FIRE-RETARDANT TREATED, IN THICKNESS INDICATED OR, IF NOT INDICATED, NOT LESS THAN 1/2-INCH THICK.

2.7 MISCELLANEOUS MATERIALS

- A. FASTENERS:
1. WHERE ROUGH CARPENTRY IS EXPOSED TO WEATHER, IN GROUND CONTACT, OR IN AREA OF HIGH RELATIVE HUMIDITY, PROVIDE FASTENERS WITH HOT-DIP ZINC COATING COMPLYING WITH ASTM A 153.
- B. METAL FRAMING ANCHORS: MADE FROM HOT-DIP, ZINC-COATED STEEL SHEET COMPLYING WITH ASTM A 653 G60 COATING DESIGNATION.
- C. BUILDING WRAP: AIR RETARDER SHEETING MADE FROM POLYOLEFINS; CROSS LAMINATED FILMS, WOVEN STRANDS, OR SPUN-BONDED FIBERS; COATED OR UNCOATED, WITH OR WITHOUT PERFORATIONS; AND COMPLYING WITH ASTM E 1677, TYPE 1.
1. MANUFACTURERS: TYVEK COMMERCIAL WRAP, BY DUPONT COMPANY, WILMINGTON, DE.
- D. SHEATHING TAPE: PRESSURE-SENSITIVE PLASTIC TAPE FOR SEALING JOINTS AND PENETRATIONS IN SHEATHING AND RECOMMENDED BY SHEATHING MANUFACTURER FOR USE WITH TYPE OF SHEATHING REQUIRED.
- E. SILL-SEALER GASKETS: GLASS-FIBER-RESILIENT INSULATIN, FABRICATED IN STRIP FORM, FOR USE AS A SILL SEALER, 1-INCH NOMINAL THICKNESS, COMPRESSIBLE TO 1/32 INCH; SELECTED FROM MANUFACTURER'S STANDARD WIDTHS TO SUIT WIDTH OF SILL MEMBERS INDICATED.
- F. TERMITE SHIELD: PROVIDE 20 GAGE SHEET METAL WITH A HOT-DIP ZINC COATING AT ALL EXTERIOR WALLS. MECHANICALLY BRAKE TO CONFIGURATION INDICATED.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. SET ROUGH CARPENTRY TO REQUIRED LEVELS AND LINES, WITH MEMBERS PLUMB, TRUE TO LINE, CUT, AND FITTED. FIT ROUGH CARPENTRY TO OTHER CONSTRUCTION; SCRIBE AND COPE AS NEEDED FOR ACCURATE FIT. LOCATE FURRING, NAILERS, BLOCKING, GROUNDS, AND SIMILAR SUPPORTS TO COMPLY WITH REQUIREMENTS FOR ATTACHING OTHER CONSTRUCTION.
- B. APPLY FIELD TREATMENT COMPLYING WITH AWPA M4 TO CUT SURFACES OF PRESERVATIVE-TREATED LUMBER AND PLYWOOD.
- C. SECURELY ATTACH ROUGH CARPENTRY WORK TO SUBSTRATE BY ANCHORING AND FASTENING AS INDICATED.
- D. FRAMING STANDARD: COMPLY WITH AFPA'S "MANUAL FOR WOOD FRAME CONSTRUCTION," UNLESS OTHERWISE INDICATED.
- E. FRAMING WITH ENGINEERED WOOD PRODUCTS: INSTALL ENGINEERED WOOD PRODUCTS TO COMPLY WITH MANUFACTURER'S WRITTEN INSTRUCTIONS.
- F. COMPLY WITH APPLICABLE RECOMMENDATIONS CONTAINED IN APA FORM NO. E30K, "APA DESIGN/CONSTRUCTION GUIDE: RESIDENTIAL & COMMERCIAL," FOR TYPES OF STRUCTURAL-USE PANELS AND APPLICATIONS INDICATED.
- G. BUILDING WRAP APPLICATION: COVER WALL SHEATHING WITH BUILDING WRAP AS INDICATED. COVER UPSTANDING FLASHING WITH 4-INCH OVERLAP. SEAL SEAMS, EDGES, AND PENETRATIONS WITH TAPE. INSERT STORING & TRUSS INSTALLATION FROM 24X36 SPECS.

SECTION 064023 - INTERIOR ARCHITECTURAL WOODWORK

PART 1 - GENERAL

1.1 SUMMARY

- A. THIS SECTION INCLUDES INTERIOR WOODWORK INCLUDING FOR THE FOLLOWING APPLICATIONS:
1. STANDING AND RUNNING TRIM.
 2. SOLID SURFACING-MATERIAL WINDOW STOOLS.
 3. PLASTIC LAMINATE WOOD SHELF AND BRACKETS.
 4. SHOP FINISHING OF WOODWORK.
- B. INTERIOR ARCHITECTURAL WOODWORK INCLUDES WOOD FURRING, BLOCKING, SHIMS, AND HANGING STRIPS UNLESS CONCEALED WITHIN OTHER CONSTRUCTION BEFORE WOODWORK INSTALLATION.

Christopher W. White
Architect AR #3086
5801 E. 41st St., Suite 712
Tulsa, Oklahoma



10-29-21

Revisions:

- C. SEE DIVISION 9 SECTION "PAINTING" FOR FIELD FINISHING.

1.2 SUBMITTALS

- A. SAMPLES:
1. LUMBER AND PANEL PRODUCTS FOR TRANSPARENT FINISH, FOR EACH SPECIES AND CUT, FINISHED ON GRADE AND TO THE EDGE.
 2. LUMBER AND PANEL PRODUCTS WITH SHOP-APPLIED OPAQUE FINISH, FOR EACH FINISH SYSTEM AND COLOR, WITH EXPOSED SURFACE FINISHED.
 3. PLASTIC-LAMINATES, FOR EACH TYPE, COLOR, PATTERN, AND SURFACE FINISH.
 4. SOLID-SURFACING MATERIALS.

1.3 QUALITY ASSURANCE

- A. QUALITY STANDARD: UNLESS OTHERWISE INDICATED, COMPLY WITH AWI'S "ARCHITECTURAL WOODWORK QUALITY STANDARDS" FOR GRADES OF INTERIOR ARCHITECTURAL WOODWORK, CONSTRUCTION, FINISHES, AND OTHER REQUIREMENTS.
1. PROVIDE AWI CERTIFICATION LABELS OR COMPLIANCE CERTIFICATE INDICATING THAT WOODWORK COMPLIES WITH REQUIREMENTS OF GRADES SPECIFIED.

1.4 PROJECT CONDITIONS

- A. ENVIRONMENTAL LIMITATIONS: DO NOT DELIVER OR INSTALL WOODWORK UNTIL BUILDING IS ENCLOSED, WET WORK IS COMPLETE, AND HVAC SYSTEM IS OPERATING AND MAINTAINING TEMPERATURE AND RELATIVE HUMIDITY AT OCCUPANCY LEVELS DURING THE REMAINDER OF THE CONSTRUCTION PERIOD.

White Design Group, P.C.
Restaurant and Interiors Consulting
5801 EAST 41ST STREET, SUITE 712, TULSA, OKLAHOMA 74135

New Restaurant Conversion For:
Arby's - 1632 AR-25 Bypass
Heber Springs, Arkansas

Sheet Content

Specifications

Sheet Number